

SuMIRE – PFS

概要、現在の仕様、技術開発、予算、スケジュールなど

Hiroshi Karoji @ IPMU




SuMIRE-PFS計画の特色



- 「最先端プログラム」からスタート
⇒ “年度”なしで2010/13の4年間
- HSCへの巨額投資をそのまま活用
⇒ 補正光学系、Prime Focus Unit
- Gemini/Caltech/JPLのdesign studyがある
⇒ すばる、Geminiともgo sign直前
⇒ しかし、高すぎる
- 装置製作の（潜在的）国際partnersが実在
⇒ Gemini studyの遺産




What should be swapped?



What should be installed?




What is SuMIRe's PFS ?




Top-Level WBS Revised

WBS Element	Institution(WFMOS)	⇒ SuMIRe PFS
1.0 Science	Caltech/JPL	Japan
2.0 Management	JPL	Japan
3.0 System Engineering	JPL	Japan/JPL :
4.0 Instrument System		
4.1 Spectrograph	Cambridge	Marseille
4.2 Positioner	JPL/PSU	JPL
4.3 Detector System	Caltech/JPL	Princeton
4.4 Fiber System	LNA	LNA :
4.5 Prime Focus Instrument	JPL	JPL/Subaru
4.6 System Software	UKATC	UK
4.7 Metrology/calibration	UCL	UK/JPL/Subaru
5.0 Integration & test	JPL	JPL/Marseille/Subaru
6.0 Data System	UKATC	UK

何故 Cambridge Spectrograph を止めたいか？



何故 New CCD を止めたいか？



PFS Performance

- *throughput budget*
- WFMOS team-B design is extremely aggressive

@790nm

Misalignment PFS/PFU	0.98	high
Fiber Positioners	0.89	keep
Fiber System	0.68	improve ?
Spectrograph	0.689	aggressive
CCD QE	0.997	too high
DE Instrument throughput	0.40	aggressive
DE Total throughput	0.21	keep !?



Where are we?

Today

\$1=¥100

- Awarded \$27M + \$2M “boost”
- \$12.5M committed to HSC
- \$16.5M available for PFS
- part of the overhead \$5M will come back to the project (see later)
- cf. WFMOS cost estimate was \$68.5M

WFMOS cost

- Total cost \$68.5M
- At our disposal \$16.5M
- Asked Seiffert (JPL) for revised estimate
- without high dispersion, WFMOS is \$56.3M, including overhead and reserves (20%)
- instrument itself is \$33.9M +reserve \$7.4M

Possible?

- Current strategy for the instrument:
 - Japan (detector and integration): \$16.5M
 - French labor: \$5M
 - Caltech/JPL fiber positioner: \$10M
 - Brazil fiber: \$5M
 - UK metrology+software: \$5M
 - total: \$41.5M
 - WFMOS-based estimate: \$33.9M

Boundary Conditions

- 「最先端」 終了時：2014年3月時点
 - ⇒ 装置がとりあえず “出来た”
 - ⇒ partial (engineering) First Light
 - ⇒ fibers 敷設と床張完了、N positioner と N/(400-500) 分光器。望遠鏡時間への impact を minimize
- Full spec. 装置の完成
 - = Survey 開始 : >2016年
 - ⇒ HSC Survey の完了と密接に関連







Figure 7.0-1: WFMOS Organization Chart

SuMIRe/PFS Organization



WFMOS Top Level Schedule





Figure 7.3-1: Top Level Schedule

Ideal Schedule as of Sep. 2010: The PM's Perspective



DE以外のサイエンス

- 2nd arm は最初から作る
⇒ 395-600nm or 1.0-1.3μm ?
- High Dispersion (20,000-40,000)は容易に後付け可能とする
⇒ “Fiber Selector”
from N to N/100-200?

